BOUNDARY CURVE TABLE					
CURVE #	DELTA	RADIUS	CHORD BEARING	CHORD LENGTH	ARC LENGTH
C1	41° 13' 18"	290.00'	S48° 45' 05"E	183.05'	187.06'
C1(R)	41° 13' 21"	289.90'	N48° 45' 34"E	204.15'	208.55'
C2	18° 17' 42"	1106.28'	S81° 23' 19"W	351.34'	352.37'
C2(R)	18° 17' 38"	1106.28'	S81° 23' 09"W	351.32'	352.36'

INTERNAL CURVE TABLE					
CURVE #	DELTA	RADIUS	CHORD BEARING	CHORD LENGTH	ARC LENGTH
C3	9° 50' 29"	1106.28'	S58° 13' 17"W	189.78'	190.02'
C4	6° 26' 13"	1106.28'	S85° 18' 34"W	122.23'	122.36'
C5(R)	87° 07' 51"	38.00'	S70° 07' 24"E	52.38'	57.79'
C6(R)	79° 30' 26"	30.00'	N13° 49' 00"E	38.66'	41.63'

LINE TABLE		
Line #	Bearing	Length
L1	S53° 18' 49"W	12.88'
L2	S71° 10' 42"E	34.23'
L3 (R)	S28° 10' 42"E	33.89'
L4 (R)	N28° 10' 42"W	44.63'

NOTES

1. BASIS OF BEARINGS – WYOMING STATE PLANE COORDINATES, EAST ZONE NAD83-2011. DISTANCES ARE GROUND DISTANCES.
2. ALL UNMONUMENTED LOT CORNERS, ANGLE POINTS, AND POINTS OF CURVATURE TO BE MONUMENTED WITH 1/2" ALUMINUM CAP STAMPED "SSS P.L.S. 5910" ON 5/8"x24" REBAR.
3. NO PORTION OF THE LANDS CONTAINED WITHIN THE PLAT BOUNDARY AS SHOWN FALL WITHIN A F.E.M.A. 100-YEAR SPECIAL FLOOD HAZARD AREA PER F.I.R.M. PANEL #56021C0985F, DATED JANUARY 17, 2007.
4. "PERPETUAL ACCESS, CIRCULATION, DRAINAGE, & UTILITY EASEMENT(S)" GRANTED HEREON TO ALL OWNERS OF LANDS CONTAINED WITHIN THE PLAT BOUNDARY FOR THE PURPOSES INDICATED.
5. "16'-WIDE ACCESS EASEMENT" GRANTED HEREON, ALONG WITH "24'-WIDE MUTUAL ACCESS, CIRCULATION, DRAINAGE, & UTILITY EASEMENT(S)" TO ALL OWNERS OF LANDS CONTAINED WITHIN THE PLAT BOUNDARY FOR REMAIN ACCESS TO WEST LINCOLNWAY (AKA US 30) AND ANY NECESSARY COMMON DRAINAGE, & UTILITY.
6. THE LANDS CONTAINED WITHIN THIS REPLAT ARE SUBJECT TO A "20' BOPU UTILITY & ACCESS EASEMENT" RECORDED ON THE 17th DAY OF MARCH, 2022 AT BOOK 5781, PAGE 1337 IN THE REAL ESTATE OFFICE OF THE COUNTY CLERK OF LARAMIE COUNTY, WYOMING.
7. THE LANDS CONTAINED HEREIN THIS REPLAT ARE SUBJECT TO A "RECIPROCAL EASEMENT AGREEMENT" RECORDED ON THE 30th DAY OF NOVEMBER, 2006 AT BOOK 1981, PAGE 2098 IN THE REAL ESTATE OFFICE OF THE COUNTY CLERK OF LARAMIE COUNTY, WYOMING.
8. BOPU EXCLUSIVE EASEMENT AREA
   a. A PORTION OF THOSE "EASEMENTS/ACCESS, CIRCULATION, DRAINAGE, & UTILITY EASEMENT(S)" GRANTED HEREON (AND ABUTTING AREAS) AS REQUIRED ARE DEDICATED EXCLUSIVELY TO THE BOARD OF PUBLIC UTILITIES OF THE CITY OF CHEYENNE (BOPU), THEIR LEGAL SUCCESSORS AND/OR ASSIGNS.
   b. 24ft BOPU EXCLUSIVE AREAS DEDICATED HEREON ARE TO BE FORMALLY GRANTED UNDER SEPARATE EASEMENT AGREEMENT AFFIDAVITS AND ARE DESCRIBED AS FOLLOWS:
   i. "24ft WATER MAIN UTILITY & ACCESS EASEMENT" EXTENDING 12 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE:
   BEGINNING AT A POINT ON THE WEST LINE OF LOT 1, BLOCK 1, HITCHING POST PLAZA, 1st FILING WHICH POINT BEARS S.28°10'42"E., ALONG SAID WEST LINE, A DISTANCE OF 33.89 FEET FROM THE NORTHWEST CORNER OF SAID LOT 1; THENCE N.61°49'18"E., A DISTANCE OF 11.83 FEET; THENCE S.28°10'42"E., A DISTANCE OF 44.63 FEET; THENCE S.61°49'18"W., A DISTANCE OF 11.83 FEET; THENCE N.28°10'42"W., A DISTANCE OF 44.63 FEET TO THE POINT OF BEGINNING OF SAID AXIS; THENCE S.61°49'18"W., A DISTANCE OF 588.86 FEET TO THE WEST LINE OF SAID LOT 1, BLOCK 1, HITCHING POST PLAZA, 1st FILING AND SAID EASEMENT THERE TERMINATES.
   THE BOUNDARY LINES OF SAID EASEMENT SHALL BE LENGTHENED OR SHORTENED TO MAINTAIN A CONTINUOUS EASEMENT NO LESS THAN 20 FEET WIDE FROM THE WEST LINE OF SAID LOT 1, TO THE WEST LINE OF SAID RIGHT-OF-WAY LINE AS SHOWN HEREON, SAID EASEMENT CONTAINING 12,316 SQUARE FEET MORE OR LESS.
   ii. "20' SANITARY SEWER MAIN UTILITY & ACCESS EASEMENT" EXTENDING 10 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE:
   BEGINNING AT A POINT ON THE WEST LINE OF LOT 1, BLOCK 1, HITCHING POST PLAZA, 1st FILING WHICH POINT BEARS S.28°10'42"E., ALONG SAID WEST LINE, A DISTANCE OF 78.52 FEET FROM THE NORTHWEST CORNER OF SAID LOT 1; THENCE N.61°49'18"E., A DISTANCE OF 588.86 FEET; THENCE N.28°10'42"W., A DISTANCE OF 20.00 FEET; THENCE S.61°49'18"W., A DISTANCE OF 588.86 FEET TO THE WEST LINE OF SAID LOT 1, HITCHING POST PLAZA, 1st FILING; THENCE N.28°10'42"E., ALONG SAID WEST LINE AND EXTENSION THEREOF, A DISTANCE OF 20.00 FEET TO THE POINT OF BEGINNING OF SAID AXIS; THENCE S.61°49'18"W., A DISTANCE OF 588.86 FEET TO THE WEST LINE OF LOT 1, HITCHING POST PLAZA, 1st FILING AND SAID EASEMENT THERE TERMINATES.
   THE BOUNDARY LINES OF SAID EASEMENT SHALL BE LENGTHENED OR SHORTENED TO MAINTAIN A CONTINUOUS EASEMENT NO LESS THAN 20 FEET WIDE FROM THE WEST LINE OF SAID LOT 1, TO THE WEST LINE OF SAID RIGHT-OF-WAY LINE AS SHOWN HEREON, SAID EASEMENT CONTAINING 12,316 SQUARE FEET MORE OR LESS.

Reception #133886
The State of Wyoming
County of Laramie
This instrument was filed for record at 4:01 o'clock P.M. on the 30 day of March A.D. 2022 and duly recorded in book ___ on page ___ Pkg 12 Ver 109
Debra K. Lee
County Clerk & Ex-Officio Register of Deeds
By Shannon Schu Deputy

VICINITY MAP



VACATION STATEMENT

IT IS THE INTENT OF THIS REPLAT TO VACATE AS SHOWN HEREON ALL OF LOT 1, BLOCK 2, CHEYENNE ICE AND EVENTS CENTER, 4th FILING, CITY OF CHEYENNE, LARAMIE COUNTY, WYOMING.

INCLUDING ALL LOT LINES AND EASEMENTS OF RECORD, UNLESS OTHERWISE NOTED HEREON.

FILING RECORD

RECORDED IN/ON/2022 AT 4:01 PM BOOK 12 PGS# 109
Debra K. Lee, CLERK OF LARAMIE COUNTY, WY PAGE 1 OF 1



LEGEND

- ○ SET 1/2" ALUMINUM CAP STAMPED "SSS P.L.S. 5910" ON 5/8" x 24" REBAR
- ⊗ FOUND 1/2" ALUMINUM CAP "SSS P.L.S. 2500"
- ⊠ FOUND 1/2" ALUMINUM CAP "SSS P.L.S. 5910"
- ● FOUND 2" ALUMINUM CAP STAMPED AS NOTED
- ◉ FOUND ALUMINUM CAP "P.E.L.S. 2817"
- ⊕ FOUND 5/8" REBAR
- ⌖ FOUND NAIL
- (M) DENOTES MEASURED DATA
- (R) DENOTES RECORD DATA
- CHEYC ___ DENOTES CHEYENNE ICE AND EVENTS CENTER, FILING #

DEDICATION

KNOW ALL PERSONS BY THESE PRESENTS THAT: 1600 Hitching Post, LLC, owner in fee simple of All of Lot 1, Block 2, Cheyenne Ice and Events Center, 4th Filing, City of Cheyenne, Laramie County, Wyoming;

Have caused the same to be surveyed, vacated, and replatted to be known as HITCHING POST PLAZA, 1st FILING and do hereby declare the subdivision of said land as it appears on this plat, to be their free act and deed and in accordance with their desires and do furthermore grant the easements as shown for the purposes indicated.

Robert Chamberlin as Member for 1600 Hitching Post, LLC

OWNER ACKNOWLEDGEMENT

STATE OF WYOMING } SS
COUNTY OF LARAMIE }

Before me, a Notary Public in and for the state and county aforesaid, personally appeared Robert Chamberlin, who, upon oath, acknowledged that he/she is a member of 1600 Hitching Post, LLC and that executed this instrument for the purposes herein contained, by signing their name as such officer.

Witness my hand and official seal this 25 day of March 2022.

Notary Public, Laramie County, Wyoming

My Commission Expires June 17 2023

APPROVALS

Approved by the City of Cheyenne Planning Director this 24th day of March 2022.

Development Director, City of Cheyenne, Wyoming

Approved by the City Engineer of the City of Cheyenne, Wyoming this 29th day of March 2022.

Mayor, City Engineer ATTEST: City Clerk

CITY ACKNOWLEDGEMENT

STATE OF WYOMING } SS
COUNTY OF LARAMIE }

Before me, a Notary Public in and for the state and county aforesaid, personally appeared Charles Bloom, City of Cheyenne Development Director, and [illegible], who, upon oath, executed this instrument for the purposes herein contained, by signing their names as such officers.

Witness my hand and official seal this 24th day of MARCH 2022.

VALERIE PICKARD
NOTARY PUBLIC
STATE OF WYOMING
COMMISSION ID: 145877
MY COMMISSION EXPIRES: 8/6/27

Notary Public, Laramie County, Wyoming

My Commission Expires AUGUST 6, 2027

HITCHING POST PLAZA, 1st FILING

AN ADMINISTRATIVE REPLAT OF
ALL OF LOT 1, BLOCK 2,
CHEYENNE ICE & EVENTS CENTER, 4th FILING
CITY OF CHEYENNE, LARAMIE COUNTY, WYOMING

PREPARED FEBRUARY 2022

CERTIFICATE OF SURVEYOR

Professional Land Surveyor JEFFREY B. JONES 5910 WYOMING 3/25/22

I, Jeffrey B. Jones, Licensed Professional Land Surveyor in the State of Wyoming, for and on behalf of Steil Surveying Services, LLC, hereby state, to the best of my knowledge, information and belief, that this map was prepared from field notes taken during an actual survey made by me or under my direct supervision; and that this map correctly shows the results of said survey and that the monuments found or set are as shown.

REVISED: 03/25/2022

\21130 HITCHING POST ALTA PAS\21130C HPP FINAL(CC).DWG

© COPYRIGHT 2022 STEIL SURVEYING SERVICES, LLC ALL RIGHTS RESERVED

STEIL SURVEYING SERVICES, LLC
PROFESSIONAL LAND SURVEYORS
PLANNING & DEVELOPMENT SPECIALISTS
1108 WEST 19th ST. CHEYENNE, WY. 82001 ○ (307) 634-7273
756 GILCHRIST ST. WHEATLAND, WY. 82201 ○ (307) 322-9789
www.SteilSurvey.com ○ info@SteilSurvey.com